

REAR FUSELAGE II - TAIL CONE FAIRING - EXTERNAL - INSPECTION/CHECK

EFFECTIVITY: ALL

1. General

- A. This section gives the procedures to do the visual inspection of rear fuselage II - tail cone fairing for general condition.
- B. Related Zone: 313.
- C. (Applicable to EMB-145 ( ) models) Zone Boundaries: STA X = 26461.57 thru STA X = 27928.5.  
(Applicable to EMB-135 ( ) models) Zone Boundaries: STA X = 22921.57 thru STA X = 24388.5.
- D. The procedures in this section are given in the sequence below. The tasks identified with (♦) are part of the Scheduled Maintenance Requirements Document (SMRD).

TASK NUMBER	DESCRIPTION	EFFECTIVITY
05-20-56-200-801-A ♦	REAR FUSELAGE II - TAIL CONE FAIR- ING - EXTERNAL GENERAL VISUAL IN- SPECTION	ALL

TASK 05-20-56-200-801-A

EFFECTIVITY: ALL

## 2. REAR FUSELAGE II - TAIL CONE FAIRING - EXTERNAL GENERAL VISUAL INSPECTION

### A. General

- (1) This task gives instructions to do SMRD Zonal Task 53-Z313-213-001-A00.
- (2) You must do the external general visual inspection (GVI) of rear fuselage II, at zone 313, within a touching distance of the items examined.
- (3) The function of the external general visual inspection (GVI) is to find damage, failure, or irregular conditions that can be easily seen.

### B. References

REFERENCE	DESIGNATION
<a href="#">AMM TASK 12-22-00-600-801-A/300</a>	LIGHT DIRT - SERVICING
<a href="#">AMM TASK 12-22-00-600-802-A/300</a>	HEAVY DIRT - SERVICING

### C. Zones and Accesses

Not Applicable

### D. Tools and Equipment

ITEM	DESCRIPTION	PURPOSE	QTY
Standard	Ladder	To get access to the area	

### E. Auxiliary Items

Not Applicable

### F. Consumable Materials

Not Applicable

### G. Expandable Parts

Not Applicable

### H. Persons Recommended

QTY	FUNCTION	PLACE
1	Does the task	Rear fuselage II - tail cone fairing

### I. Preparation

SUBTASK 841-002-A

- (1) Put the ladder in position.
- (2) If necessary, clean the inspection area ([AMM TASK 12-22-00-600-801-A/300](#)) or ([AMM TASK 12-22-00-600-802-A/300](#)) as applicable.

J. External General Visual Inspection ([Figure 601](#))

*SUBTASK 212-002-A*

- (1) Examine the tail cone fairing zone for loose rivets, nicks, cracks, dents, skin deformation, erosion, fillet sealant condition, corrosion, and deteriorated protective treatment ([Figure 601](#)).
- (2) Examine the drains for contamination and general condition.

K. Follow-on



*SUBTASK 842-002-A*

- (1) Remove the ladder.

EFFECTIVITY: ALL

Tail Cone Fairing - External General Visual Inspection

Figure 601



145AMM050074.MCE A